

Taking care of your water supply

Craigmaddie Valve Tower.

The proposal is to construct a bespoke bridge to exactly replicate the existing bridge including fixing details and rivets.

The top of parapet T-sections and deck inverted T-sections will be replaced like for like to maintain the exact U-shaped structure.

It will be painted silver grey to match the existing ironwork around the site. The bridge will be fabricated off site and transported to site for assembly in the same way the existing bridge would have been.

In addition to replacement of the bridge the ironwork on the valve tower and at the entrance to the valve tower and across the Craigmaddie spillway to the east will be stripped back, mechanically prepared, primed and repainted.



Craigmaddie Scour Valve Tower Bridge

Only minor repairs are required to remedy this. The temporary scaffolding will be removed, ironwork will all be blast cleaned, prepared and repainted.

Two of the horizontal mid railings are missing and replacements will be provided.

scottishwater.co.uk



customer.services@scottishwater.co.uk

6800 0778778



